

Detail for "Renovation of corridor and 2 class rooms in  
Department of Economics at main campus University of Kashmir".

1. Providing and Laying of Anti-Skid Ceramic / Polished vitrified floor tiles of size 600x600 mm ( thickness to be specified by the manufacture) of approved make (Somany) in all colors, shades laid on 20 mm thick bed of cement mortar 1:4 mix ( 1cement : 4 coarse sand ) including pointing the joints with matching pigment complete.

CORRIDOR

1x16'-0" x 15'-0"	=	240.00 Sfts
1x11'-6" x 12'-0"	=	138.00 "
1x50'-0" x 6'-0"	=	300.00 "
1x16'-0" x 10'-0"	=	160.00 "
1x44'-0" x 6'-0"	=	264.00 "
1x18'-0" x 10'-0"	=	180.00 "
1x11'-0" x 8'-0"	=	88.00 "
1x50'-0" x 6'-0"	=	300.00 "
1x15'-0" x 10'-0"	=	150.00 "
1x42'-0" x 5'-0"	=	252.00 "
1x18'-0" x 10'-0"	=	180.00 "
1x11'-6" x 12'-0"	=	138.00 "
1x50'-0" x 6'-0"	=	300.00 "
1x16'-0" x 10'-0"	=	160.00 "

CLASS ROOMS

2x37'-0" x 34'-0"	=	2516.00 "
-------------------	---	-----------

AT DOORS & CORNERS

12x7'-0" x 2'-0"	=	168.00 "
------------------	---	----------

SKIRTING

2x210'-0" x 0'-6"	=	210.00 "
-------------------	---	----------

TOTAL 5744.00 Sfts

*E. J. 20*  
Prof. and Head  
Deptt. of Economics  
University of Kashmir  
Srinagar